

REMOVAL OF LIRIODENDRON
TREE #5.

ALLOW TO WALL UP
EXISTING KERB DROP DOWN.

REMOVAL OF LIRIODENDRON
TREE #4.

REMOVAL OF LIRIODENDRON
TREE #3.

PATH TO BE 2% CROSSFALL
TOWARD THE STORMWATER
CHANNEL.

REMOVAL OF LIRIODENDRON
TREE #2.

2.5m WIDE 100mm 25MPa
CONCRETE FOOTPATH WITH
665 MESH ON A 150mm
COMPACTED AP40
BASECOURSE.

REMOVAL OF LIRIODENDRON
TREE #1. INCLUDING TREE
REMOVAL, ROOT REMOVAL &
BACKFILL.

NOTES:

- ALLOW TO WORK AROUND STREET LIGHTS
- ALLOW TO REMOVE AND REINSTATE BOLLARDS AND SIGNS

CONFIRM PATH LEVELS ONSITE.

RESHAPE SWALE
WHERE REQUIRED
(MAX 1 IN 4).

2.50m

83.5m

2%

2%

2%

Nelson City Council
te kaitiaki o whakatū

INFRASTRUCTURE

JOB TITLE

SAXTON PATHWAYS – HOCKEY TURF PATH



NORTH

	SURVEYED: N/A
--	---------------

DESIGNED: M CHRISTIAN

DATE: 1/04/2022

SCALE: 1:150 @ A1

NCC PLAN NUMBER
